



ADDENDUM NO. 3
to
BIDDING/CONTRACT DOCUMENTS
for
**CONSTRUCT WEST APRON EXPANSION AND
INFRASTRUCTURE AT VPS**

DESTIN-FORT WALTON BEACH AIRPORT

Okaloosa County ITB AP 51-19

TO: All Prospective Bidders

DATE: April 10, 2019

DELIVERY: Posted on bidnetdirect.com/florida and myokaloosa.com/purchasing/home

Quote Submittal Deadline: The Bid Date and submission time remains April 17, 2019 at 3:15PM (CST) as stated in a previous addendum.

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents as noted below. Acknowledge receipt of this Addendum in the space provided on Page BF-1 of the Bid Forms. Failure to do so may subject a Bidder to disqualification.

This Addendum consists of 5 pages.

I. PROJECT MANUAL

1. Bid Schedule:

- i) For Item No. 7 – Temporary Covered Walkway, the bidder is to insert a unit lump sum price of \$50,000 which will be used as an allowance for this item

II. CONSTRUCTION PLANS

For all construction plan sheets issued in addendum no. 2, replace the description in the revision block that reads “Addendum No. 1” with “Addendum No. 2”.

III. QUESTIONS/RFI's

1. On plan sheet E5.1, there are several notes that reference sheet S1.1, there is no S1.1 within the plan sets. Please advise.

RESPONSE: The contractor should disregard references to sheet S1.1. The contractor should have a licensed professional engineer prepare, and submit for review, a signed and sealed design for the pole, anchor system, and foundation for the selected fixture and pole system.



Engineer's Estimate
Construct West Apron Expansion and Infrastructure at VPS
Destin - Fort Walton Beach Airport



Item No.	Spec. No.	Item Description	Quantity	Unit	Unit Price	Amount
1	C-105	Mobilization	1	LS		\$0.00
2	C-100	Contractor Quality Control Program	1	LS		\$0.00
3	01210-1	Bid Allowance 1: For the purchase, delivery and installation of one new intercom system for the west gate, 2-360 degree security cameras mounted on light poles in the credit card parking lot and 2 -360 degree security cameras mounted on high mast light poles in the west apron expansion. Includes integration with Air Operations Center (AOC) communications and security system	1	LS	\$25,000.00	\$25,000.00
4	01210-2	Bid Allowance 2: For the purchase, delivery and installation of a flush station on the OCWS 20" water main as detailed in the plans. Includes 20" water line, fittings, valves and concrete pad.	1	LS	\$50,000.00	\$50,000.00
5	01210-3	Bid Allowance 3: For Okaloosa County Permit Fees	1	LS	\$5,000.00	\$5,000.00
6	1510-1	Engineer's Field Office	1	LS		\$0.00
7	1510-2	Temporary Covered Passenger Walkway	1	LS		\$0.00
8	01720	Project Record Documents	1	LS		\$0.00
9	S-140-1	Full Depth Asphalt Pavement Removal	9,052	SY		\$0.00
10	S-140-2	Asphalt Surface Course Removal	773	SY		\$0.00
11	S-140-3	Concrete Pavement Removal	1,510	SY		\$0.00
12	S-140-4	Remove 36" CMP Culvert	1	EA		\$0.00
13	S-140-5	Remove Water Line Flush Facility, including 20" DIP Water Pipe with Stand Pipe, Concrete Box and Pad and Riprap Apron	1	LS		\$0.00
14	S-140-6	Remove Chain Link Fence	2,306	LF		\$0.00
15	S-140-7	Remove Chain Link Fence Slide Gate and operator	1	EA		\$0.00
16	S-140-8	Remove Sanitary Sewer Lift Station, including Valve Box and Control Panel	1	LS		\$0.00
17	S-140-9	Remove Lav Cart Dump Facility, including Grinder Pump Station, Control Panel, Effluent Inlet Drain and Piping, and 2" Force main	1	LS		\$0.00
18	S-140-10	Remove Sanitary Sewer Manhole	2			\$0.00
19	S-140-11	Remove 2" PE Sanitary Sewer Force Main	755	LF		\$0.00
20	S-140-12	Remove 6" PVC Sanitary Sewer Force Main	749	LF		\$0.00
21	S-140-13	Remove 6" & 12" DIP Water Main	1,119	LF		\$0.00
22	S-140-14	Remove Existing Riprap	1	LS		\$0.00
23	S-140-15	Remove Existing Aluminum Shed	1	LS		\$0.00
24	S-140-16	Remove Existing Masonry Building with Canopy	1	LS		\$0.00
25	S-141	Asphalt Pavement Milling	11,560	SY		\$0.00
26	S-142	Pavement Marking Removal	405	SF		\$0.00
27	P-151-1	Clearing and Grubbing	6.0	AC		\$0.00
28	P-151-2	Tree Removal	21.0	EA		\$0.00
29	P-152-1	Unclassified Excavation	16,815	CY		\$0.00
30	P-152-2	Pre-Construction Survey of Phase 1 Limits of Grading	1	LS		\$0.00
31	P-154-1	6" Subbase Course	39,240	SY		\$0.00
32	P-154-2	Separation Geotextile	27,850	SY		\$0.00
33	P-209-1/P-211-1	Optional Base Course	25,904	SY		\$0.00
34	P-209-2	6" Crushed Aggregate Base Course	13,337	SY		\$0.00
35	P-209-3/P-211-2	Separation Geotextile	27,580	SY		\$0.00
36	P-304-1/P-306-1/ P-403-1	Optional Stabilized Base Course for PCC Pavement	12,326	SY		\$0.00



Engineer's Estimate
Construct West Apron Expansion and Infrastructure at VPS
Destin - Fort Walton Beach Airport



Item No.	Spec. No.	Item Description	Quantity	Unit	Unit Price	Amount
37	P-304-2/P-403-2	Optional Stabilized Base Course for Asphalt Pavement	13,386	SY		\$0.00
38	P-401	Asphalt Surface Course	3,335	TON		\$0.00
39	FDOT-334	Type SP-12.5 Asphalt Surface Course	2,035	TON		\$0.00
40	P-501-1	8" Concrete Pavement	6,180	SY		\$0.00
41	P-501-2	15" Concrete Pavement	6,146	SY		\$0.00
42	P-602	Emulsified Asphalt Prime Coat	9,583	GAL		\$0.00
43	P-603	Emulsified Asphalt Tack Coat	2,681	GAL		\$0.00
44	P-620-1	Non-Reflective Pavement Markings	12,859	SF		\$0.00
45	P-620-2	Reflective Pavement Markings	9,911	SF		\$0.00
46	P-620-3	Reflective Pavement Markings (Red Paint)	760	SF		\$0.00
47	P-620-4	Temporary Pavement Markings (Non-Reflective)	3,788	SF		\$0.00
48	F-162-1	Chain Link Fence	2,133	LF		\$0.00
49	F-162-2	Install High Density Polyethylene Slats in Existing Chain Link Fence	210	LF		\$0.00
50	F-162-3	Temporary Chain Link Fence	2,948	LF		\$0.00
51	F-162-4	Double Swing Gate (15' Opening)	4	EA		\$0.00
52	F-165-1	Cantilever Slide Gate (15' Opening)	1	EA		\$0.00
53	F-165-2	Cantilever Slide Gate (26' Opening)	1	EA		\$0.00
54	F-166-1	Linear Induction Slide Gate Operator	1	EA		\$0.00
55	F-166-2	Relocation of Existing Gate Electrical Equipment	1	LS		\$0.00
56	D-701-1	12 inch Class III RCP	33	LF		\$0.00
57	D-701-2	12 inch Class V RCP	68	LF		\$0.00
58	D-701-3	12 inch DIP	85	LF		\$0.00
59	D-701-4	12 inch DIP in Existing PCC Pavement	62	LF		\$0.00
60	D-701-5	18 inch Class III RCP	534	LF		\$0.00
61	D-701-6	18 inch Class V RCP	283	LF		\$0.00
62	D-701-7	24 inch Class III RCP	546	LF		\$0.00
63	D-701-8	24 inch Class V RCP	107	LF		\$0.00
64	D-701-9	30 inch Class V RCP	391	LF		\$0.00
65	D-701-10	36 inch Class V RCP	306	LF		\$0.00
66	D-701-11	42 inch Class V RCP	153	LF		\$0.00
67	D-701-12	54 inch Class III RCP	234	LF		\$0.00
68	D-751-1	Type C Inlet	9	EA		\$0.00
69	D-751-2	Type D Inlet	1	EA		\$0.00
70	D-751-3	Type 4 Airfield Inlet	1	EA		\$0.00
71	D-751-4	Trench Drain in Existing PCC Pavement	20	LF		\$0.00
72	D-751-5	Airfield Trench Drain	551	LF		\$0.00
73	D-751-6	Airfield Trench Drain Inlet	6	EA		\$0.00
74	D-751-7	Airfield Storm Drain Manhole	6	EA		\$0.00
75	D-751-8	Standard Storm Drain Manhole	3	EA		\$0.00
76	D-751-9	MES (4:1) for 24 inch RCP	1	EA		\$0.00
77	D-751-10	Concrete Flared End Section for 54" RCP	1	EA		\$0.00
78	D-751-11	15" Flap Gate Installed in Drainage Structure	1	EA		\$0.00
79	D-751-12	24" Flap Gate Installed in Drainage Structure	1	EA		\$0.00
80	D-751-13	36" Flap Gate Installed in Drainage Structure	1	EA		\$0.00
81	D-751-14	42" Flap Gate Installed in Drainage Structure	1	EA		\$0.00



Engineer's Estimate
Construct West Apron Expansion and Infrastructure at VPS
Destin - Fort Walton Beach Airport



Item No.	Spec. No.	Item Description	Quantity	Unit	Unit Price	Amount
82	D-751-15	Conc. Box and Pad for Water Main Flush Station	1	LS		\$0.00
83	FDOT-520	Concrete Curb, Type D	2,938	LF		\$0.00
84	FDOT-522	4" Concrete Sidewalk	347	SY		\$0.00
85	FDOT-530	Rubble Riprap	342	SY		\$0.00
86	FDOT-570-1	Sodding	2377	SY		\$0.00
87	FDOT-570-2	Performance Turf	13180	SY		\$0.00
88	FDOT-700-1	Stop Sign and Post	6	EA		\$0.00
89	FDOT-700-2	18"x24" Sign Panel Mounted on Light Pole or Column	24	EA		\$0.00
90	FDOT-700-3	ADA Single Face Accessible Parking Space Sign	2	EA		\$0.00
91	FDOT-700-4	ADA Double Face Accessible Parking Space Sign	2	EA		\$0.00
92		Bollards	6	EA		\$0.00
93	T-905	Topsoil	4,862	CY		\$0.00
94	02606-1	Standard Sanitary Sewer Manhole	3	EA		\$0.00
95	02606-2	Aircraft Rated Sanitary Sewer Manhole	3	EA		\$0.00
96		Lavatory Cart Dump Station Inlet, including concrete apron and 6" PVC Riser and Fittings	2	LS		\$0.00
97	15051-1	8" PVC Gravity Sanitary Sewer Pipe	1188	LF		\$0.00
98	15051-2	2" PVC Force Main	80	LF		\$0.00
99	15051-3	6" PVC Force Main	125	LF		\$0.00
100	15051-4	6" PVC Water Main	94	LF		\$0.00
101	15051-5	12" PVC Water Main	1275	LF		\$0.00
102	15051-6	1" Polyethylene (HDPE) Tubing	260	LF		\$0.00
103	15100-1	Fire Hydrant & Gate Valve Assembly	2	EA		\$0.00
104	15100-2	Hose Bib Assembly to include concrete filled steel bollard pipe, water line riser pipe, hose rack and painting of the base post, complete and in place	2	EA		\$0.00
105	15100-3	6" Gate Valve	1	EA		\$0.00
106	15100-4	12" Gate Valve	3	EA		\$0.00
107	32 33 17	Wastewater Lift Station	1	LS		\$0.00
108		Pre- Emergent Herbicide-2 applications & spot spray (mulch areas)	1	LS		\$0.00
109		Directional Bore- 4"	96	LF		\$0.00
110		Directional Bore- 6"	48	LF		\$0.00
111		Sch 40 PVC Sleeving	770	LF		\$0.00
112		Irrigation 3" RPZ Backflow w/Cover, Ball & Master Valves, POC, Etc.	1	LS		\$0.00
113		Irrigation- Hunter Pro-C 12 Station Controller	1	LS		\$0.00
114		Irrigation Zones- ICV Valve, Wiring, Pipe, Heads, Fittings, Etc.	11	EA		\$0.00
115		Tree - October Glory Maple 45 Gal. 10'-12' Ht. (includes staking)	8	EA		\$0.00
116		Tree- Duraheat River Birch 45 Gal. 10'-12' Ht. (includes staking)	11	EA		\$0.00
117		Tree- Little Gem Magnolia 45 Gal. 7'-8' Ht. (includes staking)	9	EA		\$0.00
118		Tree- Sand Live Oak 2" Cal min. 11'-12' Ht. (includes staking)	29	EA		\$0.00
119		Tree- Shumard Oak 3" Cal. Min. 12'-14' Ht. (includes staking)	6	EA		\$0.00
120		Centipede Sod- labor & material- irrigated areas per plan	42,044	SF		\$0.00
121		Centipede Sod Unit Price- for additional disturbed areas if requested	1	SF		\$0.00
122		Pinestraw Mulch for Tree Circles	1	LS		\$0.00



Engineer's Estimate
Construct West Apron Expansion and Infrastructure at VPS
Destin - Fort Walton Beach Airport



Item No.	Spec. No.	Item Description	Quantity	Unit	Unit Price	Amount
123		Hardscape- Fido & Me Fountain Ultrasite-PBARK-498 w/ Labor	1	EA		\$0.00
124		Hardscape-6 Ft. Bench Ultrasite-PBARK-940S-P6 w/ Labor	2	EA		\$0.00
125		Hardscape- Trash Receptacle Ultrasite PL-32, FTR-32-08, IG KIT	2	EA		\$0.00
126		Hardscape- Pet Waste Station Ultrasite PBARK-488, IG KIT w/ Labor	1	EA		\$0.00
127		Hardscape- 8'x8' Cantilevered Umbrella Ultrashade M- Shade w/ Labor	1	EA		\$0.00
128		Hardscape- "Pet Relief Area" Post Sign 5'-6' O.A. Ht. w/ Labor	2	EA		\$0.00
129		Maintenance- 1 Year Maintenance & Warranty	1	LS		\$0.00
130		Covered Walkway (Includes Canopy Structure, Foundations and 4" Sidewalk)	1	LS		\$0.00
131		Bus Shelter (Including 4" Sidewalk)	2	LS		\$0.00
132	L-105-1	Electrical Demolition	1	LS		\$0.00
133	L-108-1	Cable - L-824 5kV, #8 AWG Type C	2640	LF		\$0.00
134	L-108-2	Counterpoise with Conduit/Duct	1305	LF		\$0.00
135	L-110-1	1W-2" PVC Direct-Bury	490	LF		\$0.00
136	L-110-2	1W-2" PVC Concrete-Encased	815	LF		\$0.00
137	L-125-1	High Mast Light Pole & Foundation	6	EA		\$0.00
138	L-125-2	High Mast Fixture	12	EA		\$0.00
139	L-125-3	Elevated LED MITLs	6	EA		\$0.00
140	L-260521	Panelboard Modifications	1	LS		\$0.00
141	L-260521	GSE Rack & Power Center	1	LS		\$0.00
142	L-260521	Fiber Optic Cable	330	LF		\$0.00
143	L-260521	Cat-6 Cable	140	LF		\$0.00
144	L-260521	2-#12 AWG THWN-2, W/G	660	LF		\$0.00
145	L-260521	2-#10 AWG THWN-2, W/G	6090	LF		\$0.00
146	L-260521	#10 AWG GND	230	LF		\$0.00
147	L-260521	#6 AWG THWN-2	460	LF		\$0.00
148	L-260521	#2 AWG THWN-2	2100	LF		\$0.00
149	L-260521	#2 AWG GND	50	LF		\$0.00
150	L-260521	#1 AWG THWN-2	4960	LF		\$0.00
151	L-260521	#1 AWG GND	1240	LF		\$0.00
152	L-260521	3/4" PVC in Canopy Structure	500	LF		\$0.00
153	L-260541	1" PVC CE Under Pavement	3820	LF		\$0.00
154	L-260541	1" PVC DB in Soil	2020	LF		\$0.00
155	L-260541	2" PVC DB in Soil	180	LF		\$0.00
156	L-260541	2-1/2" PVC DB in Soil	1250	LF		\$0.00
157	L-260541	Handholes	19	EA		\$0.00
158	L-265600	Parking Fixture, Pole and Foundation	34	EA		\$0.00
159	L-265600	Wall-Mount, Bus Stations	4	EA		\$0.00
160	L-265600	Canopy Lights	26	EA		\$0.00
161	L-330523	Directional Bore, 1W-2" dia.	650	LF		\$0.00
162	L-330523	Directional Bore, 2W-2" dia.	290	LF		\$0.00

TOTAL=	\$80,000.00
---------------	--------------------